

Grenzwerte der Hüllkurven Sieblinie 1 bis 3

Sieb 1 4/32mm			
Zugabestelle: Niederkassel, Steinerne Bänke, Walsum, Wardt/Rees			
Korn- durch- messer in [mm]	Sieb 1	Grenzwerte in [Massen-%]	
		von	bis
63,0	100	100	100
56,0	100	98	100
45,0	99	90	100
31,5	95	75	100
22,4	86	55	97
16,0	75	37	93
8,0	41	12	78
5,6	27	5	60
4,0	18	2	40
2,0	8	1	20
1,0	5	1	10
0,063	0,7	0,1	1,0

Sieb 2 4/90mm			
Zugabestelle: Emschermündung, Mehrum			
Korn- durch- messer in [mm]	Sieb 2	Grenzwerte in [Massen-%]	
		von	bis
100,0	100	99	100
90,0	98	95	100
63,0	95	87	100
56,0	94	83	99
45,0	92	75	98
31,5	85	57	96
22,4	77	43	93
16,0	62	30	89
8,0	35	10	70
5,6	26	5	55
4,0	18	3	40
2,0	8	2	20
1,0	5	1	10
0,063	0,7	0,1	1,0

Sieb 3 2/16mm			
Zugabestelle: Niedermörmter			
Korn- durch- messer in [mm]	Sieb 3	Grenzwerte in [Massen-%]	
		von	bis
45,0	100	100	100
31,5	99	98	100
22,4	97	92	98
16,0	90	80	95
8,0	63	35	82
5,6	47	18	67
4,0	31	10	53
2,0	15	4	27
1,0	7	1	12
0,063	0,7	0,1	1,0